

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-21148-00-01
Spot: SWSW Sec/Twnshp/Rge: 31-34S-22W
660 feet from S Section Line, 660 feet from W Section Line
Lease Name: COBBLESTONE Well #: 31 1R
County: CLARK Total Vertical Depth: 5823 feet

Operator License No.: 33392
Op Name: KEITH F. WALKER OIL & GAS CO., LLC
Address: 219 STANLEY ST PO BOX 1725
ARDMORE, OK 73401

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5533		WITH 10 SX CMT
SURF	8.625	732		189.25
COND	20	64		
PROD	4.5	5823	2309	WITH 185 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/16/2009 9:00 AM
Plug Co. License No.: 33311 Plug Co. Name: PHIL DOLLAR OILFIELD SERVICES, INC.
Proposal Rcvd. from: STEVE DIXON Company: KEITH WALKER OIL & GAS Phone: (580) 223-1575

Proposed Plugging Method: CIBP ON TBG & 10 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2009 9:40 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5533' WITH 10 SX CMT. 1ST PLUG LOAD HOLE WITH GEL WATER & PUMPED 50 SX CMT AT 760'. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
5586	5600		
11-6-09 2010060454 RECEIVED SEP 28 2009			

Remarks: USED 60/40 POZMIX 4% GEL BY PHIL DOLLAR OILFIELD SERVICES.

Plugged through: TBG

KCC WICHITA

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED

SEP 22 2009

KCC DODGE CITY

Form CP 2/3