

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-185-22132-00-00  
Spot: SENE SW Sec/Twnshp/Rge: 9-23S-14W  
1650 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: BEAVER Well #: 2  
County: STAFFORD Total Vertical Depth: 4040 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	430		WITH 350 SX CMT
PROD	5.5	4038	2390	WITH 150 SX CMT <u>131.30</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/15/2009 1:30 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 3900' & 5 SX CMT. PLUG AT 890' WITH 15 SX GEL & 50 SX CMT. PLUG AT 460' WITH 50 SX CMT. PLUG AT 40' TO SURFACE.

Plugging Proposal Received By: JERRY W. STAPLETON Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/15/2009 3:10 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3880' & DUMPED 5 SX CMT ON TOP OF SAND WITH A DUMP BAILER. 1ST PLUG AT 890' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 460' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3964	3971		
3952	3960		

11-6-09  
2010060455

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

RECEIVED

SEP 28 2009

KCC WICHITA

District: 01

Signed Richard M. Lacey  
(TECHNICIAN)

RECEIVED  
SEP 22 2009  
KCC DODGE CITY