

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-02081-00-00
Spot: NENESE Sec/Twnshp/Rge: 30-22S-11W
2970 feet from N Section Line, 330 feet from E Section Line
Lease Name: KOMAREK V Well #: 7
County: STAFFORD Total Vertical Depth: 3582 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: 312 N. BUFFALO
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	13	220		WITH 225 SX CMT
PROD	5.5	3553	0	WITH 200 SX CMT

116.42

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/17/2009 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BOTTOM TO 3500' & 6 SX CMT. BOND LOG TOP OF HOLE. IF BOND LOG SHOWS CMT FILL 6" WITH CMT FROM 600'-0'. TOP OFF 13" X 6" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY Witness Type: PARTIAL
Date/Time Plugging Completed: 09/17/2009 12:05 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED BOTTOM TO 3424' & 6 SX CMT WITH DUMP BAILER. BOND LOG INDICATED CMT FROM 580' TO 20'. RAN 1" TBG TO 20' INSIDE THE 13" X 6" ANNULUS. PUMPED 15 SX CMT, CIRCULATING TO SURFACE. RAN 2 3/8" TBG IN 6" TO 600'. PUMPED 120 SX CMT CIRCULATING TO SURFACE. PULLED TBG & TOPPED OFF 6" WITH 18 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3553	3561		

11-6-09
2010060456

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

SEP 28 2009

KCC WICHITA

District: 01

RECEIVED
SEP 22 2009
KCC DODGE CITY

Signed Richard M. Lacey
(TECHNICIAN)

Form CR 2/3