

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-02113-00-00
Spot: NENENE Sec/Twnshp/Rge: 31-22S-11W
330 feet from N Section Line, 330 feet from E Section Line
Lease Name: HEYEN B Well #: 7
County: STAFFORD Total Vertical Depth: 3568 feet

Operator License No.: 32432
Op Name: LA VETA OIL & GAS, LLC
Address: 312 N. BUFFALO
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	13	235		WITH 225 SX CMT
PROD	6	3546	0	WITH 200 SX CMT 115.96

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/16/2009 8:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: SAND BOTTOM TO 3500' & 6 SX CMT WITH BAILER. RAN TBG TO 600' IN 6". CIRCULATE CMT TO SURFACE. TOP OFF CMT IN 13"X6" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2009 11:05 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

IN 1977 1" RAN TO 575' DOWN 13" X 6" & CMT CIRCULATED TO SURFACE.SANDED BOTTOM TO 3490' & DUMPED 6 SX CMT WITH DUMP BAILER. RAN 1" TBG TO 120' INSIDE THE 13" X 6" ANNULUS TAGGING CMT. PUMPED 75 SX CMT DOWN TBG CIRCULATING UP 13" TO SURFACE. RAN 2 3/8" TBG TO 600'. PUMPED 95 SX CMT CIRCULATING CMT TO SURFACE UP 6". PULLED TBG OUT OF HOLE. TOPPED OFF 6" WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3546	3568		

11-6-09
2010060456

RECEIVED
SEP 28 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
SEP 22 2009
KCC DODGE CITY