

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-101-22187-00-00
Spot: SENWSWNW Sec/Twnshp/Rge: 22-19S-29W
1815 feet from N Section Line, 550 feet from W Section Line
Lease Name: MUMMA Well #: 1-22
County: LANE Total Vertical Depth: 4730 feet

Operator License No.: 31783
Op Name: MID-CONTINENT ENERGY OPERATIN
Address: 100 W 5TH ST STE 450
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	306		WITH 170 SX CMT

153.73

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/10/2009 4:15 AM
Plug Co. License No.: 5822 Plug Co. Name: VAL ENERGY, INC.
Proposal Rcvd. from: RANDY MARTIN Company: VAL ENERGY, INC. Phone: (316) 263-6688

Proposed Plugging Method: 1ST PLUG AT 2190' WITH 50 SX CMT. 2ND PLUG AT 1410' WITH 80 SX CM.T 3RD PLUG AT 690' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 09/10/2009 6:15 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 2190' WITH 50 SX CMT. 2ND PLUG AT 1410' WITH 80 SX CM.T 3RD PLUG AT 690' WITH 50 SX CMT. 4TH PLUG AT 330' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

11-6-09
2010060458

RECEIVED
SEP 28 2009
KCC WICHITA

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
SEP 18 2009
KCC DODGE CITY