

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-23412-00-00
Spot: NWNESE Sec/Twnshp/Rge: 5-9S-18W
2150 feet from S Section Line, 1100 feet from E Section Line
Lease Name: COPHER Well #: 1-5
County: ROOKS Total Vertical Depth: 3561 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N WATER STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3345		115.73
SURF	8.625	235	0	160 SX CMT, 3% CC, 2% GEL.
T1	2.375	3345		
PC		1446		
PROD	4.5	3559	0	190 SX CMT, AA2 PREMUIUM, 10% SALT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/21/2009 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: STAN FROETSCHNER Company: MURFIN DRILLING CO., INC. Phone: (785) 483-5371

Proposed Plugging Method: Ordered 275 sxs 60/40 pozmix - 4% gel - 500# hulls.
P.C. at 1446' w/175 sxs.

Plugging Proposal Received By: DARREL DIPMAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/21/2009 9:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Hooked onto 8 5/8". Pumped 15 sxs 60/40 pozmix - 4% gel.
S.I.P. 300#.
Hooked onto 4 1/2" casing. Pumped 225 sxs 60/40 pozmix - 4% gel with 500# hulls.
S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3410	3412		
3394	3396		
3370	3373		
3352	3354		
3300	3304		
3282	3283		
3255	3259		
3218	3219		

11-6-09
2010060460

RECEIVED
SEP 25 2009
KCC WICHITA

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #3809.

Plugged through: CSG

District: 04

Signed _____

Pat Bedore

(TECHNICIAN)

CM

SEP 22 2009

MURFIN DRILLING CO
WICHITA KS 67202

WILDCAT

5-09S-18W
2150' FSL & 1100' FEL, SEC

#1-5 COPHER

site 3-3/4 N & 2 W OF PLAINVILLE KS city: ROOKS API 15-163-23412
contr: MURFIN DRILLING #16 field: WC (BOXELDER NW DISC)
geol: KEVIN C. DAVIS
fr spd drig card last
date 06/24/2004 date 12/28/2004 comp 01/05/2005 issued 05/09/2005 revised 05/09/2005

ELV: 2038 KB, 2033 GL
tops.....depth/datum
PBSD3338 -1300
RTD.....3560 -1522
NO TOPS RPTD

IP status
OIL, LKC, INTV NA, 03/01/2005
CSG: 8-5/8" 235 (ALT 2), 4-1/2" 3559, MULTI STAGE COLLAR
AT 1446 / 175 SX
COMMENT: WELL LOC BASED ON 3-D SEISMIC INTRPRTN;
PERMIT DEADLINE EXTENDED 12/22/2004
NO CORES
DSTS TAKEN - DETAILS NA
TRGT ZN: LKC, ARB (OIL), PTD 3500 (ARB), MICT - CO, PF
(LKC) INTV NA, SWB DWN, GSO, POP, OIL WELL
(POTENTIAL NOT RPTD), DOFP 3/1/2005 - TIGHT HOLE - NO
OTHER INFO AVAILABLE - TEMP COMP 5/9/2005

COPYRIGHT 2004
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS