

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-00188-00-00
Spot: SE Sec/Twnshp/Rge: 9-23S-38W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: WIDNER Well #: 1
County: KEARNY Total Vertical Depth: 2723 feet

Operator License No.: 32864
Op Name: XTO ENERGY INC.
Address: 210 PARK AVE STE 2350
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	332		WITH 200 SX CMT
PROD	5.5	2710	0	WITH 200 SX CMT <u>88.50</u>

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/08/2009 8:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PUMP 50 SX CMT W/HULLS @ 2660'. CEMENT PLUG 2000'-2100' (ANHYDRITE @ 2050'), CUT OFF CASING AT FREEPOINT & PUMP A 100' CEMENT PLUG (50' ABOVE AND 50' BELOW CASING STUB), CEMENT PLUG 230'-380' (SURFACE CASING & BTW), CEMENT PLUG 4'-34' (AT SURFACE), WELD ON IDENTIFICATION PLATE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/10/2009 1:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

9/8/09: PUMPED 100# HULLS & 50 SX CMT AT 2634'. 9/9/09: TAGGED TOC @ 2485'.
1ST PLUG AT 2150' WITH 25 SX CMT. 2ND PLUG AT 1300' WITH 20 SX CMT.
TAGGED TOC @ 1180'. PRESSURED 5 1/2" TO 600 PSI. HELD OK. PERFORATE 5 1/2"
@ 1000'. SDON. 9/10/09: INTO 5 1/2" CASING PUMPED 170 SX CMT @ 400-600 PSI.
NO BLOW, NO CIRCULATION UP ANNULUS. PUMPED 45 SX CMT DOWN
ANNULUS. PRESSURED TO 400 PSI.

Perfs:

Top	Bot	Thru	Comments
2680	2684		
2668	2678		
2651	2652		
2618	2632		

11-9-09
2010060472
RECEIVED
OCT 01 2009
KCC WICHITA

Remarks: USED CLASS C CMT W/2% GEL BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed: Jack MacLaskey
(TECHNICIAN)

RECEIVED
SEP 22 2009
KCC DODGE CITY