

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-05537-00-00
Spot: NESESE Sec/Twnshp/Rge: 4-22S-8W
975 feet from S Section Line, 439 feet from E Section Line
Lease Name: MAYER B Well #: 3
County: RICE Total Vertical Depth: 3419 feet

Operator License No.: 34058
Op Name: MUSGROVE ENERGY INC.
Address: 1121 N PRENTICE RD
PONCA CITY, OK 74604

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	206		140 SX
PROD	5.5	3376	1800	100 SX

B 111.12

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/11/2009 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: SHANE JONES Witness Type: NONE
Date/Time Plugging Completed: 09/11/2009 12:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

SET CIBP @ 3321' & CAP WITH 5 SX'S CEMENT, CUT CASING OFF AT 1800' & PULL TO 1200' & PUMP 35 SX'S CEMENT, PULL CASING TO 700' & PUMP 35 SX'S CEMENT, PULL CASING TO 250' & CIRCULATE CEMENT TO 0'. PULL CASING OUT & TOP OFF. USED 170 SX'S TOTAL.

Perfs:

11/9/09
2010060462

Remarks: 60-40 POZ, 4% GEL. COPELAND C-32925

Plugged through: CSG

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 23 2009

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

ix

PST