

State of Kansas



15-051-30248-00-00

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg.  
WICHITA, KANSAS 67202

RECEIVED  
MAY 10 1966  
CONSERVATION DIVISION  
WICHITA, KANSAS

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Pfannenstiel of Lebem Drilling Co. has this

date requested permission to plug the following described well:

Mr. Pfannenstiel guarantees payment of the plugging fee.

Operator's full Name: Shenandoah Oil Corporation

Complete Address: 406 Mutual Savings Building, Wichita, Kansas *74 Worth, TEXAS*

Lease Name: Schoenthaler Well No. 1

Location: SW SE NE Sec. 3 Twp. 12 Rge. 20 (E)(W) X

County Ellis Total Depth 3893 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Pfannenstiel was instructed to plug the well as follows:

Jet Pits circulate hvy mud, set cementing plug at 500 ft. and  
displace 20 sax cement thru drill pipe, heavy mud to 200 ft.  
set cementing plug and displace 20 sax cement thru drill pipe,  
heavy mud to 40 ft. set cementing plug, 1/2 sax hulls and 10 sax  
cement, cementing to base of cellar. plug rat hole with two sax cem.

Very truly yours,

*Leo Massey*  
Conservation Division Agent