

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-025-20306-00-01  
Spot: SENE Sec/Twnshp/Rge: 21-34S-21W  
3326 feet from S Section Line, 677 feet from E Section Line  
Lease Name: BARBY Well #: 1-21  
County: CLARK Total Vertical Depth: 5540 feet

Operator License No.: 5055  
Op Name: C. H. TODD, INC.  
Address: 1000 N TYLER STE 100  
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4236		WITH 2 SX CMT
CIBP		4360		
SURF	8.625	802		WITH 450 SX CMT 180.05
COND	13.38	210		WITH 300 SX CMT
PROD	5.5	5526	2400	WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/07/2009 10:00 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4236' WITH 2 SX CMT. PLUG AT 840' WITH 15 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/07/2009 11:15 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

CIBP @ 4236' WITH 2 SX CMT. 1ST PLUG AT 850' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. CMT FELL TOPPED OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5406	5452		
5383	5386		
4500			
4286	4293		

INVOICED  
DATE 11-17-09  
INV. NO. 2010060507

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY OIL WELL CEMENTING.

Plugged through: TBG

District: 01

RECEIVED  
OCT - 9 2009  
KCC DODGE CITY

Signed Jerry W. Stapleton  
(TECHNICIAN)  
PART II

RECEIVED  
OCT 15 2009  
KCC-WICHITA  
PK