

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20428-00-00
Spot: NWSEWNE Sec/Twnshp/Rge: 1-20S-2W
4443 feet from S Section Line, 1951 feet from E Section Line
Lease Name: MINNIE JOHNSON Well #: 2
County: MCPHERSON Total Vertical Depth: 3425 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	163		100 SXS CMT
PROD	5.5	3424		100 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/12/2009 11:00 AM
Plug Co. License No.: 31528 Plug Co. Name: KELSO, MIKE OIL, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS & CAP WITH 5 SXS CEMENT. PUMP 35 SXS CEMENT AT 450'. CIRCULATE TO SURFACE FROM 250'.
111.31

Plugging Proposal Received By: GREG EVES Witness Type: PARTIAL
Date/Time Plugging Completed: 10/12/2009 11:00 AM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 3250' AND CAPPED WITH 5 SXS CEMENT. PULLED CASING TO 1282' AND PUMPED 35 SXS CEMENT. PULLED CASING TO 440' AND PUMPED 35 SXS CEMENT. PULLED CASING TO 260' AND PUMPED 80 SXS TO CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3401	3402		

INVOICED

DATE 11-17-09
INV. NO 2010060512

RECEIVED
OCT 16 2009
KCC WICHITA

Remarks: COPELAND CEMENTING TICKET #C3948 TOTAL = 150 SXS 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed Greg Eves
(TECHNICIAN)

4K

PKT