

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-20799-00-00
Spot: E2NWNWNE Sec/Twnshp/Rge: 1-20S-2W
4950 feet from S Section Line, 2145 feet from E Section Line
Lease Name: MINNIE JOHNSON Well #: B-3
County: MCPHERSON Total Vertical Depth: 3455 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3002		
SURF	8.625	165		100 SXS CMT
PROD	5.5	3425		100 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/06/2009 11:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 50' ABOVE TOP PERFS AND CAP WITH 5 SXS OF CEMENT. PULL CASIG TO 450' AND CIRCULATE TO SURFACE.
112.29

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 10/06/2009 3:00 PM KCC Agent: GREG EVES

Actual Plugging Report:

SANDED TO 2885' AND CAPPED WITH 5 SXS CEMENT. CUT PIPE AT 1624' AND PULLED CASING TO 454' AND PUMPED 35 SXS. PULLED CASING TO 255' AND PUMPED 140 SXS TO CIRCULATE TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3397	3398		
2958	2971		

INVOICED
DATE 11-17-09
INV. NO. 2010060512

RECEIVED
OCT 14 2009
KCC WICHITA

Remarks: COPELAND CEMENTING TICKET #C32946. TOTAL = 175 SXS 60/40 POZ 4% GEL

Plugged through: CSG

District: 02

Signed *Greg Eves*
(TECHNICIAN)

PE