

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24706-00-00  
Spot: SWNESE Sec/Twnshp/Rge: 11-20S-26W  
1360 feet from S Section Line, 1315 feet from E Section Line  
Lease Name: JAMES Well #: 2-11  
County: NESS Total Vertical Depth: 4522 feet

Operator License No.: 6039  
Op Name: L.D. DRILLING, INC.  
Address: 7 SW 26TH AVE  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	347		WITH 225 SX CMT
PC		1776		W/250 SX
PROD	4.5	4516	0	WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/29/2009 9:00 AM  
Plug Co. License No.: 6039 Plug Co. Name: L.D. DRILLING, INC.  
Proposal Rcvd. from: MIKE KASSELMAN Company: L.D. DRILLING, INC. Phone: (620) 793-3051

Proposed Plugging Method: PUMP 300# HULLS, 40 SX CMT & GEL TO 1800'. THEN CMT TO SURFACE. USE 50 SX CMT FOR BACKSIDE.

146.97

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 09/29/2009 10:30 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 40 SX CMT & 300# HULLS, THEN 14 SX GEL & 120 SX CMT. MAXIMUM PRESSURE 900#. SHUT IN PRESSURE 600#. TIED ONTO BACKSIDE & PUMPED 10 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4516	4522	OH	

INVOICED  
DATE: 11-17-09  
INV. NO. 2010060515

RECEIVED  
OCT 15 2009  
KCC-WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND CEMENTING.

Plugged through: CSG

District: 01

Signed Michael Maier  
(TECHNICIAN)

RECEIVED  
SEP 30 2009

KCC DODGE CITY