

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-23647-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 28-23S-25E
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: WIMMER Well #: 13-28
County: BOURBON Total Vertical Depth: 400 feet

Operator License No.: 5786
Op Name: MCGOWN DRILLING, INC.
Address: PO BOX K
MOUND CITY, KS 66056

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20	0	

35.00

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/07/2009 12:00 PM
Plug Co. License No.: 5786 Plug Co. Name: MCGOWN DRILLING, INC.
Proposal Rcvd. from: DOUG MC GOWAN Company: MCGOWN DRILLING, INC. Phone: (913) 795-2258

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED BORE TO 400'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D. AND TO CIRCULATE THE WELL FULL OF CEMENT FROM 250' TO SURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 10/07/2009 2:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

DRILL PIPE WAS RAN INTO THE WELL TO 400'. THE WELL WAS GELLED FOR BRIDGING PURPOSES. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE DRILL PIPE TO 400'. THE PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE DRILL PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE DRILL PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

Perfs:

RECEIVED
KCC DISTRICT #3

OCT 7 2009 CPT

CHANUTE, KS

INVOICED
DATE 11-17-09
INV. NO. 2010060517

RECEIVED
OCT 15 2009
KCC WICHITA

Remarks:

Plugged through: DP

District: 03

Signed Clayton P. Titel
(TECHNICIAN)