

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22169-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 3-32S-39W
4950 feet from S Section Line, 1980 feet from E Section Line
Lease Name: MLP YOUNGGREN A Well #: 2
County: STEVENS Total Vertical Depth: 6200 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5300		
SURF	8.625	1710		WITH 510 SX CMT
DVT		3228		WITH 275 SX CMT
PROD	5.5	6200	375	WITH 575 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/11/2009 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed
Plugging
Method:

PUMP 100# HULLS & 25 SX CMT INTO PERFS. 50 SX CMT AT 1750'. 40 SX CMT AT 580'. 10 SX CMT TO SURFACE.

201.50

Plugging Proposal Received By: JACK MACLASKEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/16/2009 4:00 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

9/11/09: PUMP 200# HULLS & 25 SX CMT. 9/14/09: FREEPOINT INDICATED 5 1/2" LOOSE @ 400'. RAN CMT BOND LOG FROM 1800' TO 180'. INDICATED POOR CMT FROM 400' TO 1800'. 9/15/09: RIH W/TBG & PUMPED 25 SX CMT @ 1740'. POOH W/TBG. SHOT 5 1/2" @ 375'. PULLED OUT 5 1/2". RIH W/TBG TO 600'. 9/16/09: PUMPED 65 SX CMT. PUMPED 10 SX CMT AT 40'.

Perfs:

Top	Bot	Thru	Comments
5467	5476		
4686	4692		

INVOICED
DATE 11-17-09
INV. NO. 20100 60518

RECEIVED
OCT 15 2009

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

KCC WICHITA *PPT*

District: 01

Signed Jack MacLaskey
(TECHNICIAN)

RECEIVED
OCT - 1 2009
KCC DODGE CITY

[Signature]
Form CP 2/3