

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24581-00-00
Spot: SWSWSE Sec/Twnshp/Rge: 36-18S-25W
540 feet from S Section Line, 2310 feet from E Section Line
Lease Name: DICK HORCHEM Well #: 2-36
County: NESS Total Vertical Depth: 4414 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	201		WITH 160 SX CMT
PC		1665		WITH 130 SX CMT
PROD	5.5	4403	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/07/2009 8:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: BILLY BRINEY Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: PUMP 25SX CMT & 200# HULLS. PULL TBG TO 1700' & CIRCULATE TO SURFACE. PULL TBG & TOP OFF WITH CMT. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE.

143.40

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/07/2009 12:15 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4275' & PUMP 25 SX CMT & 200# HULLS. PULL TBG TO 1700' & PUMP 165 SX CMT. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 25 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

RECEIVED

OCT - 9 2009

KCC DODGE CITY

Signed

Michael Maier
(TECHNICIAN)

INVOICE
DATE: 11-17-09
INV. NO. 2010060520

RECEIVED
OCT 15 2009
KCC WICHITA

Form CP-3/3