

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24969-00-00
Spot: SENWSWNE Sec/Twnshp/Rge: 14-16S-22W
1710 feet from N Section Line, 2010 feet from E Section Line
Lease Name: BISAGNO TRUST Well #: #1-14
County: NESS Total Vertical Depth: 4392 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	213		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/01/2009 10:00 AM
Plug Co. License No.: 4958 Plug Co. Name: MALLARD, J. V., INC.
Proposal Rcvd. from: CAROL NICHOLS Company: MALLARD, J. V., INC. Phone: (620) 241-4640

Proposed Plugging Method: 1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

142.74

Plugging Proposal Received By: JACK MACCLASKEY Witness Type: NONE
Date/Time Plugging Completed: 10/01/2009 12:00 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

1ST PLUG AT 1800' WITH 50 SX CMT. 2ND PLUG AT 1050' WITH 80 SX CMT. 3RD PLUG AT 500' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

INVOICE
DATE: 11-17-09
SERV. NO. 2010060520

RECEIVED
OCT 15 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY OIL WELL CEMENTING.

Plugged through: DP

District: 01

RECEIVED
OCT - 2 2009
KCC DODGE CITY

Signed

Jack MacClaskey
(TECHNICIAN)

Form CP-233

PKT