

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-011-20996-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 2-24S-21E
3070 feet from S Section Line, 2475 feet from E Section Line
Lease Name: FRANKLIN Well #: 5-81
County: BOURBON Total Vertical Depth: 650 feet

Operator License No.: 3728
Op Name: KENT, ROGER DBA R J ENTERPRISES
Address: 22082 NE NEOSHO RD
GARNETT, KS 66032

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20	0	
PROD	2	650	0	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/13/2009 3:00 PM
Plug Co. License No.: 3728 Plug Co. Name: KENT, ROGER DBA R J ENTERPRISES
Proposal Rcvd. from: JASON KENT Company: R.J. ENTERPRISES Phone: (785) 448-6995

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 650' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE CASING FULL OF CEMENT.

35.00

Plugging Proposal Received By: CLAYTON TITEL Witness Type: NONE
Date/Time Plugging Completed: 08/13/2009 5:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

1" PIPE WAS RAN INTO THE 2" CASING TO T.D.. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

INVOICED
DATE: 11-17-09
BY NO: 2010060523

RECEIVED
KCC DISTRICT #3
OCT 07 2009 CPT
CHANUTE, KS

RECEIVED
OCT 15 2009
KCC WICHITA

Remarks:
Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)

PPT