

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-001-02142-00-00
Spot: SWNESE Sec/Twnshp/Rge: 36-24S-17E
1650 feet from S Section Line, 980 feet from E Section Line
Lease Name: MILLER Well #: 2
County: ALLEN Total Vertical Depth: 814 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8	20	0	
PROD 2		270	0	
PROD 2		814	0	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/28/2009 1:30 PM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: BERNIE RUCKER Company: SOUTHERN STAR Phone: (316) 431-7582

Proposed Plugging Method: THIS WELL CONSISTED OF 2" CASING TO 814' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. A BOND LOG SHOWED A QUESTIONABLE BOND AT APPROXIMATELY 650'. THE PLUGGING PROPOSAL WAS TO PERFORATE THE 2" CASING AND TO CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/07/2009 10:00 AM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

THE 2" CASING WAS PERFORATED AT 650' AND AT 690'. 1" PIPE WAS RAN INTO THE 2" CASING TO 814'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. THE CEMENT PUMP WAS CONNETED DIRECTLY TO THE 2" CASING. CEMENT WAS 100 SAKS OF CEMENT WERE PUMED INTO THIS WELL.

Perfs:

Top	Bot	Thru	Comments
650	690	CSG	

INVOICED
NOV. 11-17-09
INV. NO. 2010060525

RECEIVED
OCT 16 2009
KCC WICHITA

RECEIVED
KCC DISTRICT #3

OCT 12 2009 CPT

CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed Clayton P. Titel
(TECHNICIAN)