

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-23824-00-00  
Spot: N2SESENE Sec/Twnshp/Rge: 28-25S-5E  
2005 feet from N Section Line, 330 feet from E Section Line  
Lease Name: HEGBERG A Well #: 203  
County: BUTLER Total Vertical Depth: 2618 feet

Operator License No.: 5030  
Op Name: VESS OIL CORPORATION  
Address: 1700 WATERFRONT PKWY BLDG 500  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	260		150 SX CMT
T1	2.375	0		
PROD	4.5	769	<u>336</u>	135 TOC-380'

Well Type: OH DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/17/2009 8:00 AM  
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.  
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method:

AS PER KCC RULES & REGS

85.09

Plugging Proposal Received By: DUANE KRUEGER  
Date/Time Plugging Completed: 09/17/2009 1:00 PM

Witness Type: NONE  
KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 50 SXS CLASS A 3% CC AND DISPLACED IN CASING ON WIRELINE @ 400', SHUT IN PRESSURE 300#. WAITED 2 HRS, TAGGED CEMENT @ 415', CUT 5-1/2" CASING @ 336', LAYED DOWN 8 JOINTS 5-1/2" CASING. RIH W/TBG @ 310'. CONSOLIDATED ESTABLISHED CIRCULATION AND MIXED AND PUMPED 120 SXS CLASS A CEMENT TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 9/17/2009, 1:00 PM.

Perfs:

Top	Bot	Thru	Comments
656	673	CSG	ADMIRE 650
542	552	CSG	ADMIRE 550

RECEIVED  
11-17-09  
2010060526

RECEIVED  
OCT 15 2009  
KCC WICHITA

Remarks: CONSOLIDATED CEMENT TICKET #23069.

Plugged through: TBG

District: 02

Signed

Duane Krueger  
(TECHNICIAN)

PKT

JK