

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

RECEIVED SEP 22 2009 KCC WICHITA

Form CP-4 December 2003 Type or Print on this Form Form must be Signed All blanks must be Filled

Lease Operator: R.R. Abderhalden

Address: 100 S. Main, Suite 510, Wichita, Kansas

Phone: (316) 262-3411 Operator License #: 5394

Type of Well: Oil Docket #: NA (Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 7-13-09 (Date)

by: Duane Krugger (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Mississippi Depth to Top: 3067 Bottom: 3140 T.D. 3140

Depth to Top: Bottom: T.D.

Depth to Top: Bottom: T.D.

API Number: 15-035-21,134-0000

Lease Name: Werner "B"

Well Number: 3

Spot Location (QQQQ): SW - SE - SE -

330 Feet from North South Section Line

990 Feet from East West Section Line

Sec. 31 Twp. 32 S. R. 6 East West

County: Cowley

Date Well Completed: 4-30-77

Plugging Commenced: 7-13-09

Plugging Completed: 8-06-09

Show depth and thickness of all water, oil and gas formations.

Table with columns: Oil, Gas or Water Records (Formation, Content) and Casing Record (Surface Conductor & Production) (From, To, Size, Put In, Pulled Out)

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole.

Dumped 35 gals. sand on bottom. Dumped 5 sax cement on sand. Top cement at 2980 ft. Shot pipe at 1838 ft and 1716 ft. Could not pull. Shot pipe at 1676 ft and pulled casing. Ran tubing to 350 ft. and cemented with 117 sax. Next day top cement was 30 ft. down. Cemented with 12 sax to surface.

Name of Plugging Contractor: R.R.A., INC. License #: 5656

Address: 100 S. Main, Suite 510, Wichita, Kansas

Name of Party Responsible for Plugging Fees: R.R. Abderhalden

State of Kansas County, Sedgwick, ss.


R.R. Abderhalden (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) R.R. Abderhalden

(Address) 100 S. Main, Suite 510, Wichita, Kansas 67202

SUBSCRIBED and SWORN TO before me this 22nd day of September, 2009

Verdella Lewis My Commission Expires: 6-6-10 Notary Public



**STATE DRILLERS' LOG**

FORM C-2

STATE CORPORATION COMMISSION - CONSERVATION DIVISION

247 North Water  
Wichita, Kansas 67202

**R. R. A., INC.**  
**No. 1-A Werner**  
**SW SE SE**

DATA AND AFFIDAVIT

See Section 31-32-6E Surface or Drive Pipe and required by Rule 82-2-123 of the Commission  
Cowley Co., Kansas Section 55-126, 55-127 and 55-128, 1947 Supplement to G. S. Kansas  
(1935)

Commenced: 3/17/77  
LE/ Completed: 3/20/77 Inc.

Surface Casing: 165'  
of 8-5/8" casing, cemented  
w/70 ex cement, 2% Gel, 3% cc  
3/14/77 67202

OFFICE ADDRESS 1649 Victoria/KSBAT Bldg., Wichita,

FORMATION Werner 'A'

WELL NO. DEPTH COUNTY Cowley

FORMATION	WELL NO.	DEPTH	COUNTY	Cowley	(W)
Surface Hole ON SW SE SE	SEC 0	- FWL 165'	S	RGE. 6E	(E)
Sand & Shale	165	- 465			
Shale & Sand	465	- 1119			
Shale, Lime & Sand	1119	- 1655			
Shale & Lime	1655	- 2148			
Shale & Sand	2148	- 2460			
Shale, Lime & Sand (Rotary) Tools	2460	- 2904	14-77		
Lime & Shale	2904	- 3092			
Lime SURFACE HOLE DATA	3092	- 3140	R.T.D.		

Size of Hole 12 1/2" (See number or (used) size 8-5/8" w/l)

I do here by certify that the foregoing statements are true and correct to the best of my knowledge and belief.

DON B DRILLING, INC.

*James L. Donelson*  
JAMES L. DONELSON

RECEIVED  
SEP 22 2009  
KCC WICHITA

STATE OF KANSAS: ss:

Subscribed and sworn to before me this 28th day of March, 1977.

*Ella Priess*  
Ella Priess, Notary Public

