

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 5364
Name: Beren Corporation
Address 1: P.O. Box 723
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: Mark Leiker
Phone: (785) 628-6101
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
4523 Depth to Top: 4553 Bottom: 4523 T.D. 4553
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. ~~15~~ - 15-135-21674 - 0000
Spot Description: KCC PT PERFECT MAT
SE-SE-SE Sec. 10 Twp. 16 S. R. 26 East West
2310 Feet from North / South Line of Section
280 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ness
Lease Name: Levi Well #: 2
Date Well Completed: 9/18/79
The plugging proposal was approved on: 9/2/09 (Date)
by: Richard Lacey (KCC District Agent's Name)
Plugging Commenced: 9/4/09
Plugging Completed: 9/4/09

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------|---|-------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| Mississippi | | Surface | 8 5/8 | 321 | None |
| | | Production | 5 1/2 | 4523 | None |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up to 5 1/2 casing. Pump 40 saks 60/40 4% with 3% cc with 200# hulls followed by 16 saks jell spacer to 2000'. Rig up Perf-Tech, ran bond log, top of cement at 1270'. Let bottom plug set 2 hours. Perforate 2 holes at 1175', pump 190 saks 60/40 4% down 5 1/2" CASING. SHUT IN AT 500#, Pump 125 saks 60/40 4% down 8 5/8, shut in at 200#. Plugging witnessed by Mike Maier.

RECEIVED
SEP 14 2009

Plugging Contractor License #: 5363 Name: Berexco, Inc.
Address 1: P.O. Box 723 Address 2: P. O. Box 20380, Wichita, KS 67206
City: Hays State: KS Zip: 67601 + _____
Phone: (785) 628-6101
Name of Party Responsible for Plugging Fees: Berexco, Inc.
State of Kansas County, Sedgwick, ss.
Mark Leiker Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Mark Leiker

[Handwritten signature]