

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County, Sec. 23 Twp 16 Rge 20 (E) W (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C. NL. NW/4

Lease Owner Nadel and Gussman

Lease Name Rogers Well No. 2

Office Address P. O. Box 309, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed 3-7-1952

Application for plugging filed 3-7-1952

Application for plugging approved 3-7-1952

Plugging commenced 3-7-1952

Plugging completed 3-7-52

Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3850 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				10-3/4"	158	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Hole filled with heavy mud from 3850' to 158'
Set plug with 10 sacks cement on top, filled hole with mud to top and set plug with 5 sacks of cement

3-22-1952

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Reserve Drilling Company

Address 703 Union National Bank Bldg.

Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

L. C. Hay (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Hay

703 Union National Bank Bldg.

(Address)

SUBSCRIBED AND SWORN to before me this 10th day of March 1952


[Signature]

Notary Public.

Nov. 3, 1952

My commission expires

23-8390-s 6-51-20M



WELL LOG

Nadel and Gussman

ROGERS No. 2

C NL NW 23-10S-20W
Rooks County, Kansas

Comm: 2-24-52

Comp: 3-7-52

Casing: 10-3/4" 158' w/115 sax

Formations	Depth
Clay, sand and shale	162
Shale and shells	500
Shale, shells and sand	1420
Shale, shells and red bed	1658
Anhydrite	1700
Broken lime and shale	2335
Lime and shale	3540
Lime	3706
Lime and shale	3739
Lime, Conglomerate	3800
Conglomerate	3818
Arbuckle	3850

Geological Tops

Heebner	3478
Toronto	3498
Lansing-Kansas City	3518 (-1279)
Conglomerate	3768
Simpson Shale	3807
Arbuckle	3817 (-1278)
Total Depth	3850
D & A	

STATE OF KANSAS)
) SS:
COUNTY OF SEDGWICK)

L. C. Hay, of law ul age, deposes and states that the above formations and depths are correct as shown by the daily drilling log of the Rogers No. 2 well in the Center of the North Line of the NW/4 of 23-10-20W, Rooks County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 10th day of March, 1952.

Thela Bass
Notary Public

My commission expires Nov. 3, 1952

~~3-22-1952~~
3-22-1952

PLUGGING
FILE SEC 22 T 10 R 20 W
BOOK PAGE 19 LINE 20