

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME Rogers

WELL NUMBER 1

330 Ft. from S Section Line

330 Ft. from ^W~~S~~ Section Line

SEC. 23 TWP. 10S RGE. 20 (X) or (W)

COUNTY Rooks

Date Well Completed 3-14-51

Plugging Commenced 10-2-91

Plugging Completed 10-2-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Nadel and Gussman

ADDRESS 3200 First National Tower, Tulsa, OK 74103

PHONE# (918) 583-3333 OPERATORS LICENSE NO. 5337

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on July 30, 1991 (date)

by David P. Williams (KCC District Agent's Name).

Is ACO-1 filed? n/a If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 3775 Bottom 3779 T.D. 3779

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

RECEIVED
STATE CORPORATION COMMISSION
10-9-1991

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil & water	0	160	8-5/8	160	0
		0	3775	5-1/2	3775	0

OCT 09 1991

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Hooked on to 5-1/2 casing and pumped 2 sks of hulls followed by 190 sks cement. Shut-in @ 400 psi. Hooked on to 8-5/8 casing and pumped 2 sks of hulls followed by 100 sks cement. SIP 200 psi.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor C & L Well Service License No. 08052

Address Box 162, Plainville, KS 67663

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Nadel and Gussman

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Joe G. Anderson (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Joe Anderson

(Address) 3200 First National Tower
Tulsa, OK 74103

SUBSCRIBED AND SWORN TO before me this 7th day of October, 19 91

Kathy Garrow Kathy Garrow
Notary Public

My Commission Expires: 8-1-95

WELL LOG

Nadel and Gussman

Rogers No. 1

330'S and 330'W
NEc NW/4 23-10-20W
Rooks County, Kansas

Comm. 3- 4-51
Comp. 3-14-51

Casing: 8-5/8" 160' w/115 Sax
5-1/2" 3775' @/100 Sax

<u>Formation</u>	<u>Depth</u>
Surface	160
Shale and shells, Red bed and sand	1010
Shale, sand and shells	1120
Sand	1370
Shale and shells	1642
Anhydrite	1684
Shale and Red bed	1765
Shale, shells and broken lime	2130
Broken lime	2405
Broken lime and shale	2550
Shale and lime	2640
Lime (broken)	2675
Shale and shells	2745
Shale and lime	3298
Lime	3450
Shale and lime	3485
K.C. lime (cherty)	3517
Lime	3685
Lime and shale	3755
Shale and sand	3772
Arbuckle lime	3779

Geological Tops

Topeka	3263
Heebner	3446
Toronto	3467
Lansing	3485
B. Kansas City	3696
Conglomerate	3728
Simpson Shale	3763
Arbuckle	3772
T.D.	3779

RECEIVED
STATE COMBINATION COMMISSION
10-9-1991
OCT 09 1991

Geological Division
Wichita, Kansas

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS:

L. C. Hay, of lawful age, deposes and states that the above formations and depths are true and correct as taken from the daily drilling log of the Rogers No. 1 well in the NW/4 of Sec. 23-10S-20W, Rooks County, Kansas.

L. C. Hay

Subscribed and sworn to before me this 16th day of March, 1951.

W. L. [Signature]
Notary Public

My commission expires 11-3-52