

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Rooks County, Sec. 23 Twp. 10S Rge. (E) 20 (W)

Location as "NE/CNW%SW%" or footage from lines SW SW SW

Lease Owner PETROLEUM, INC.,

Lease Name PAGE "C" Well No. 1

Office Address ROUTE #2, GREAT BEND, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE

Date well completed JAN. 3 19 65

Application for plugging filed JAN. 3 19 65

Application for plugging approved JAN. 3 19 65

Plugging commenced JAN. 3 19 65

Plugging completed JAN. 4 19 65

Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well ELDON PETTY, BOX 326, HAYS, KANSAS

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3770 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	219'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

MUDDERED UP WITH HEAVY MUD THRU DRILL PIPE TO 210' FOLLOWED BY A WOODEN PLUG AND 20 SACKS CEMENT. MUDDERED UP WITH HEAVY MUD TO 40', FOLLOWED BY A WOODEN PLUG, 1/4 SACK HULLS AND 10 SACKS CEMENT TO BASE OF WELL CELLAR.

RECEIVED
STATE CORPORATION COMMISSION
1-28-1965
JAN 28
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY

Address ROUTE #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
MONTE CHADD (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) MONTE CHADD, DIST. PROD. SUPT.

ROUTE #2, GREAT BEND, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 25 day of JANUARY, 19 65

My commission expires OCTOBER 19, 1968

Notary Public.

WELL LOG

COMPANY Petroleum, Inc.

SEC. 23 T. 10S R. 20W

FARM Page NO. C-1


LOC. SW SW SW

TOTAL DEPTH 3770'

COUNTY Rooks

COMM. 12-28-64 COMP. 1-6-65

CONTRACTOR Garvey Drilling Company



CASING 8 5/8" @ 219' w/180 sx

ELEVATION 2185' DF

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

- 80' Top Soil and Sand
- 220' Shale
- 700' Blue Shale
- 1085' Shale and Sand Streaks
- 1103' Shale
- 1315' Sand
- 1635' Shale and Shells
- 1672' Anhydrite
- 2110' Shale
- 2490' Shale and Lime
- 2820' Lime and Shale
- 2915' Shale and Lime
- 3090' Sandy Lime
- 3445' Lime and Shale
- 3680' Lime
- 3746' Lime and Shale
- 3770' Arbuckle
- 3770' RTD

RECEIVED
 STATE CORPORATION COMMISSION
 1-28-1965
 JAN 28 1965
 CONSERVATION DIVISION
 Topeka, Kansas

State of Kansas }
 County of Barton } RS

I, Sam N. Stephens of Garvey Drilling Company

upon oath state the above and foregoing is a true and correct copy of the log of the Page C-1 well.

Sam N. Stephens

Subscribed and sworn to before me this 18th day of January 19 65

My Commission Expires: October 19th, 1968

David S. [Signature]
 NOTARY PUBLIC