


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 23 Twp. 10 Rge. (E) 20 (W)
Location as "NE/CNW/SW" or footage from lines SENESEW 1/2
Lease Owner Herman Geo. Kaiser, Oil Producer
Lease Name _____ Page _____ Well No. 1
Office Address 909 Palace Bldg., Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed December 15, 19 57
Application for plugging filed December 14, 19 57
Application for plugging approved December 14, 19 57
Plugging commenced December 14, 19 57
Plugging completed December 14, 19 57
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3845 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	203	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud to 600 ft., 20 sacks cement. Heavy mud to 190 ft., set plug - 1/3 sack hulls and 15 sacks cement. Mudded to 40 ft. - 1/3 sack hulls, set plug and 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION
12-21-1957
DEC 21 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, Inc.
Address 709 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick ss.
L. C. Sponenberg (employee of contractor) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg
(Address) _____

SUBSCRIBED AND SWORN TO before me this 17th day of December, 19 57

My commission expires February 13, 1960 _____ Notary Public.

PLUGGING
DEC 23 10 R 204
BOOK PAGE 69.11 E 29

15-163-03093-00-00

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


COMPANY **Roman Geo. Haiger, Oil Producer**

SEC. **23** T. **10** R. **20**
 LOC. **38807A**

FARM **Page** NO. **1**

COUNTY **Rock**

TOTAL DEPTH **3045 ft.**
 COMM. **12/17/57** COMP. **12/15/57**
 SHOT OR TREATED
 CONTRACTOR **E-30, Inc.**
 ISSUED



CASING
 20 10
 15 8 303'
 12 6
 13 5

ELEVATION **2223 E.A.**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Surface Soil, Sand & shale	130
Shale	203
Concret	
Shale & shells with sand streaks	1000
Shale & shells with sand streaks and heavy streaks Iron Pyr.	1285
Sand	1375
Shale & Shells, w/Red Bed	1571
Anhydrite	1715
Shale & shells	2080
Shale w/Lime streaks	2335
Lime & Shale	2562
Ft. Wiley Lime	2610
Lime & Shale	3524
Cherty H. G. Lime	3562
H. C. Shale & Lime	3596
H. C. Lime	3730
Lime - Shale - Chert	3790
Conglomerate	3045

FORMATION TOPS:

Topoka	3253
Rebner	3483
Lansing	3501

RECEIVED
 STATE CORPORATION COMMISSION
 12-21-1957
 DEC 21 1957
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

E-30, INC.

[Signature]

STATE OF KANSAS)
)
 COUNTY OF SPENCER)

Subscribed and sworn to before me, a notary public, in and for said county and state this 17th day of December 1957.

[Signature]

My Commission expires February 13, 1960.

PLUGGING
 FILE SEC 23 T. 10 R. 20
 BOOK PAGE 69 LINE 29