


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 23 Twp. 10 Rge. 20 (X) W (W)
Location as "NE/CNW/SW" or footage from lines. SE NE NW
Lease Owner Nadel and Gussman
Lease Name Rogers Well No. 3
Office Address 1714 First National Building, Tulsa, Okla.
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed 2-8-57
Application for plugging filed 2-8-57
Application for plugging approved 2-8-57
Plugging commenced 2-8-57
Plugging completed 2-8-57
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3830 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	210'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy mud from total depth to 200' - set plug with 200 sax cement -

Set top plug at 40' with 10 sax cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Reserve Drilling Company, Inc.
Address 625 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. G. McNeil (employee of owner) ~~(owner of operator)~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. G. McNeil
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of February, 1957

My commission expires Nov. 3, 1960

Notary Public.

PLUGGING
SEC 23 T. 10 R20W
BOOK 139 L. 40

RECEIVED
STATE CORPORATION COMMISSION
FEB 15 1957

WELL LOG

Nadel and Gussman

Rogers No. 3

SE NE NW 23-10-20W

Rooks County

Kansas

Comm: 1-29-57

Comp: 2- 8-57

Casing: 8-5/8" 210' w/120 sax

Formations

Depth

Shale 217
 Shale and shells 970
 Sand and shale 1375
 Shale and shells 1649
 Anhydrite 1690
 Shale, red bed, shells 1990
 Shale and shells 2210
 Shale and lime 3380
 Lime 3785
 Cherty Conglomerate 3795
 Chert, lime and shale 3830

Geological Tops

Heebner Shale 3460
 Toronto 3482
 Lansing 3497
 Base Kansas City 3706
 Conglomerate 3754
 Eros. Simpson 3779
 Arbuckle 3825

STATE OF KANSAS

COUNTY OF SEDGWICK

} SS:

E. G. McNeil, of lawful age, states that the above formations and depths are correct to his best knowledge and belief.

E. G. McNeil

Subscribed and sworn to before me this 12th day of February, 1957.

RECORDED
2-15-1957

Nola Babb
Nola Babb, Notary Public

My commission expires Nov. 3, 1960

23 10 20W
 139 40