

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30762
Name: Oil Company of America, Inc
Address 1: 1200 Main St, Ste 101
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: Darrel Herl
Phone: (785) 625-3800
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
L/KC Depth to Top: 3478' Bottom: 3454' T.D. 3612'
L/KC Depth to Top: 3338' Bottom: 3344' T.D. 3612'
L/KC Depth to Top: 3320' Bottom: 3327' T.D. 3612'

API No. 15 - 051-03199-00-00
Spot Description: NW/4
SW NW NW Sec. 13 Twp. 15 S. R. 18 East West
4,290 Feet from North / South Line of Section
4,950 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis Leikerts Twin T0 2
Lease Name: T-S Leiker Well #: 9
Date Well Completed: April 4, 1956
The plugging proposal was approved on: April 2, 2009 (Date)
by: Steve Bond (KCC District Agent's Name)
Plugging Commenced: 8/05/2009 @ 11:30 AM
Plugging Completed: 8/05/2009 @ 6:10 PM

KCC District Agent's Name

Show depth and thickness of all water, oil and gas formations.

| Oil, Gas or Water Records | | Casing Record (Surface, Conductor & Production) | | | |
|---------------------------|---------|---|--------|---------------|------------|
| Formation | Content | Casing | Size | Setting Depth | Pulled Out |
| L/KC | Oil | Surface Pipe | 8 5/8" | 1168' | None |
| | | Production Casing | 5 1/2" | 3612' | 2009' |
| | | | | | |
| | | | | | |

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Pulling unit sanded off bottom to 3100' w/5 sxs cement.
Perf-Tech shot 5 1/2" prod. csg off @ 2200', still stuck. Shot csg again @ 2009'.
Pulled csg to 1689', Allied Cementing pumped 150 sxs cmt & 200 hulls.
Pulled csg to 1175', pumped 40sxs cmt w/100 hulls.
Pulled csg to 550', pumped 40 sxs cmt.
Pulled csg to 150' & circulated 45 sxs cmt to surface, hole stayed full of cement.
Total of 280 sxs cement & 300# hulls.

RECEIVED
SEP 16 2009

KCC WICHITA

Plugging Contractor License #: 32810 Name: Professional Pulling Services, LLC
Address 1: PO Box 486 Address 2: _____
City: Hays State: KS Zip: 67601 + 0486
Phone: (785) 628-7443

Name of Party Responsible for Plugging Fees: Darrel Herl
State of Kansas County, Ellis, ss.
Roger L. Moses (Agent) Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Roger L. Moses Agent

Handwritten initials/signature