

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 30762
Name: Oil Company of America, Inc
Address 1: 1200 Main St, Suite 101
Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Contact Person: Darrel Herl
Phone: (785) 625-3800
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
L/KC Depth to Top: 3299' Bottom: 3523' T.D. 3620'
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 051-03202-0000
Spot Description: NW/4
NW SW NW Sec. 13 Twp. 15 S. R. 18 East West
3,630 Feet from North / South Line of Section
4,950 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Ellis
Lease Name: TS Leiker Well #: 12
Date Well Completed: March 8, 1957
The plugging proposal was approved on: August 24, 2009 (Date)
by: Case Morris (KCC District Agent's Name)
Plugging Commenced: August 25, 2009 9:00 am
Plugging Completed: August 25, 2009 11:00 pm

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
<u>L/KC</u>	<u>Oil/Water</u>	<u>Surface Pipe</u>	<u>8 5/8"</u>	<u>1174'</u>	<u>None</u>
		<u>Production Casing</u>	<u>5 1/2"</u>	<u>3619'</u>	<u>1960'</u>

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ordered 375 sxs cement & 500 hulls.
Sanded off perfs to 50' above and dump bailed 5 sxs cmt on top.
Shot casing off @ 1960'.
Pulled csg to 1750', pumped 150 sxs cmt w/300 hulls.
Pulled csg to 1175', pumped 40sxs cmt w/100 hulls.
Pulled csg to 550', pumped 40 sxs cmt w/100 hulls.
Pulled csg to 150', circulated to surface w/75 sxs cmt.
Pulled rest of csg, cellar full of cmt.
Total of 305 sxs cmt and 500 hulls.

RECEIVED
SEP 16 2009

KCC WICHITA

Plugging Contractor License #: 32810 Name: Professional Pulling Services, LLC
Address 1: PO Box 486 Address 2: _____
City: Hays State: KS Zip: 67601 + _____
Phone: (785) 628-7443

Name of Party Responsible for Plugging Fees: Darrel Herl, Oil Company of America, Inc
State of Kansas County, Ellis, ss.
Roger L. Moses (Agent) Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Roger L. Moses

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

original