

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION OIL & GAS CONSERVATION DIVISION WELL PLUGGING RECORD K.A.R. 82-3-117

Form CP-4 March 2009 Type or Print on this Form Form must be Signed All blanks must be Filled

OPERATOR: License #: 30762 Name: Oil Company of America, Inc Address 1: 1200 Main St, Suite 101 Address 2: City: Hays State: KS Zip: 67601 Contact Person: Darrel Herl Phone: (785) 625-3800 Type of Well: (Check one) [X] Oil Well [ ] Gas Well [ ] OG [ ] D&A [ ] Cathodic [ ] Water Supply Well [ ] Other: [ ] SWD Permit #: [ ] ENHR Permit #: [ ] Gas Storage Permit #: [ ] Is ACO-1 filed? [ ] Yes [ ] No If not, is well log attached? [ ] Yes [ ] No Producing Formation(s): List All (If needed attach another sheet) L/KC Depth to Top: 3295' Bottom: 3521' T.D. 3591'

API No. 15 - 051-03193-0000 Spot Description: NW/4 SW NW NW Sec. 13 Twp. 15 S. R. 18 [ ] East [X] West 4,290 Feet from [ ] North / [X] South Line of Section 4,950 Feet from [X] East / [ ] West Line of Section Footages Calculated from Nearest Outside Section Corner: [ ] NE [ ] NW [X] SE [ ] SW County: Ellis Lease Name: TS Leiker Well #: 2 Date Well Completed: April 16, 1954 The plugging proposal was approved on: August 24, 2009 (Date) by: Case Morris (KCC District Agent's Name) Plugging Commenced: August 24, 2009 10:00 am Plugging Completed: August 24, 2009 1:00 pm

Show depth and thickness of all water, oil and gas formations.

Table with 6 columns: Oil, Gas or Water Records (Formation, Content), Casing Record (Surface, Conductor & Production) (Casing, Size, Setting Depth, Pulled Out). Rows include L/KC Oil/Water with Surface Pipe (8 5/8", 1168') and Production Casing (5 1/2", 3585').

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Ordered 450 sxs cement & 500 hulls. Tied to 5 1/2" csg, pumped 50sxs cement, followed with 320 sxs cement & 500 hulls. Pressured to 1000 psi Max, 800 lpsi shut-in. Tied to 8 5/8" x 5 1/2" annulus & pumped 65sxs cement to 500 psi max, 200 psi shut-in. Total of 435 sxs 60/40 poz mix, 4% gel & 500 lbs hulls.

RECEIVED SEP 16 2009 KCC WICHITA

Plugging Contractor License #: 32810 Name: Professional Pulling Services, LLC Address 1: PO Box 486 Address 2: City: Hays State: KS Zip: 67601 Phone: (785) 628-7443 Name of Party Responsible for Plugging Fees: Darrel Herl, Oil Company of America, Inc State of Kansas County, Ellis, ss. Roger L. Moses (Agent) [X] Employee of Operator or [ ] Operator on above-described well

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Roger L. Moses

Handwritten initials/signature