

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be signed
All blanks must be filled

4058
OPERATOR: License #: 5048
Name: American Warrior Inc.
Address 1: PO Box 399
Address 2: _____
City: Garden City State: KS Zip: 67846+
Contact Person: Kevin Wiles
Phone: (620) 275 2963
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (if needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 025-20268-00-01
Spot Description: _____
SE SW NW Sec. 29 Twp. 31 S. R. 21 East West
2040 Feet from North / South Line of Section
725 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Clark
Lease Name: Moore Well #: 8
Date Well Completed: 11-12-84
The plugging proposal was approved on: 7-30-09 (Date)
by: Eric MacLaren (KCC District Agent's Name)
Plugging Commenced: 8-4-09
Plugging Completed: 8-10-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
			8 5/8	633	—
			5 1/2	4761	2997

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Mixed 300 lb. hulls + 25 sx cmt. to plug perfs from 4420 to 4220.
Shot + pull 5 1/2 to 1100. Attempt to circ. hole w/mud. Mixed 50 sx plug
1100 to 950. Pull to 660. Mixed 50 sx 660 to 510. No circ. Tag
plug @ 518. Pull to 280. Mixed 30 sx 280 to 190 - no circ. WOC Tag
plug @ 254. Ran 5 1/2 to 140. Circ. hole w/mud + mixed 41 sx 140 to 0.
Cmt dropped to 25. Mixed 6 sx 25 to 0. Capped 8 5/8 3 ft. below G.L.

Plugging Contractor License #: 31151 Name: Sargent + Horton Plugging Inc.
Address 1: Rt 1 Box 49 BA Address 2: _____
City: Tyrone State: OK Zip: 73951 + 9731
Phone: (580) 854 6515

Name of Party Responsible for Plugging Fees: American Warrior, Inc
State of Kansas County: Franklin, ss.
Nancy E Davis, Compliance Coordinator Employee of Operator or Operator on above-described well,
(Print Name)

being first duty sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: _____
Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
SEP 16 2009
KCC WICHITA