

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 6569
Name: Carmen Schmitt, Inc.
Address 1: P.O. Box 47
Address 2: _____
City: Great Bend State: KS Zip: 67530 + _____
Contact Person: Curtis Hitschmann
Phone: (620) 793-2540
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 163-22319 - 0000
Spot Description: _____
NE SW NW _____ Sec. 29 Twp. 7 S. R. 17 East West
1,650 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Rooks
Lease Name: Schruben W Well #: 1
Date Well Completed: 3/7/1984
The plugging proposal was approved on: 8/27/2009 (Date)
by: Bruce Rodie (KCC District Agent's Name)
Plugging Commenced: 8/28/2009
Plugging Completed: 8/31/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		Surface	8-5/8"	1187'	0'
		Production	5-1/2"	3349'	1797.48'

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

8/28/09 - Drive to location. Tailgate safety meeting. Pull slips out of casing head. Pull stretch in casing - 10" of stretch. Rig up bailer. Run bailer to tag sand. Sand @ 2200'. Clean tools. Shut down. Drive home. 8/31/09 - Drive to location. Tailgate safety meeting. Wait on loggers. Pull stretch - shot pipe off @ 2380'. Work pipe - would not come loose. Shot pipe off @ 1785' - pipe was free. Pull 1 jt. Cement first plug @ 1758' w/150 sacks cement - 200# hulls. Pull 14 jts to second plug @ 1200' w/40 sacks of cement - 100# hulls. Pull 13 jts to third plug @ 675' w/50 sacks of cement - 100# hulls. Pull 12 jts to last plug @ 150' w/60 sacks of cement - 100# hulls to circulate cement. Pull the rest of casing - 5 jts for a total of 45 jts. Wash up jacks & tongs. Clean tools. Rack up casing jacks. Rig down. Total feet of casing pulled - 1797.48'.

Plugging Contractor License #: 6901 Name: D.S. & W. Well Servicing, Inc.
Address 1: 1822 24th Street Address 2: _____
City: Great Bend State: Kansas Zip: 67530 + _____
Phone: (620) 793-5838
Name of Party Responsible for Plugging Fees: Carmen Schmitt, Inc.
State of Kansas County, Barton, ss.
Edward S. Nemnich Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Edward S. Nemnich

RECEIVED

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

SEP 09 2009

KCC WICHITA