

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 5363  
Name: Berexco, Inc.  
Address 1: P.O. Box 723  
Address 2: P.O. Box 20380, Wichita, KS 67206  
City: Hays State: KS Zip: 67601 + \_\_\_\_\_  
Contact Person: Curtis Gabel  
Phone: ( 785 ) 628-6101  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
3062' Depth to Top: 3408' Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15 - N/A 163-00271-00-03  
Spot Description: SE-NW-SE  
C SE NW SE Sec. 28 Twp. 8 S. R. 17  East  West  
3,630 Feet from  North /  South Line of Section  
1,650 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Rooks  
Lease Name: Stamper Well #: B-3 3-28  
Date Well Completed: 7-31-81  
The plugging proposal was approved on: 7-26-09 (Date)  
by: Case Morris (KCC District Agent's Name)  
Plugging Commenced: 7-29-09  
Plugging Completed: 7-29-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
TOP.	28'	Surface	8 5/8	1328'	None
TOR	3'	Production	4 1/2	3528'	None
ICE.	204'				
Pleasanton sand	14				

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Rig up Perf Tech shoot 2 holes at 1750', 1325' and 550'. Run open ended tubing stacked out at 2766'. Tubing at 2753', spot 60 sx 60/40 pos 10% gel 150# hulls. Tubing at 1835' spot 60 sx 60/40 pos 10% gel 150# hulls. Tubing at 914 spot 60 sx 60/40 pos 10% gel circulate cemet to surface on 4 1/2. Hook to 4 1/2, pump 105 sx 60/40 pos 10% gel circulate cement to surface on 8 5/8. Shut in 8 5/8, pump 15 sx 60/40 pos 10% gel working pressure to 200#. Shut well in, rig down move off.

Plugging Contractor License #: 5363 Name: Berexco, Inc.  
Address 1: P.O. Box 723 Address 2: P.O. Box 20380, Wichita, KS 67206  
City: Hays State: KS Zip: 67601 + \_\_\_\_\_  
Phone: ( 785 ) 628-6101  
Name of Party Responsible for Plugging Fees: Berexco, Inc.  
State of Kansas County, Sedgwick, ss.  
Curtis Gabel  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Curtis Gabel

RECEIVED

SEP 18 2009

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

KCC WICHITA