

Notice: Fill out COMPLETELY
and return to Conservation Division at
the address below within
60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33874
Name: Custer Oil & Gas, LLC
Address 1: Post Office Box 628
Address 2: _____
City: Barnsdall State: OK Zip: 74002 + 0628
Contact Person: Norma Standridge
Phone: (918) 847-2531
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: old inj well SWD Permit #: D-26381
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 125-24010-0000
Spot Description: _____
SWSWSW SE Sec. 12 Twp. 34 S. R. 13 East West
165 Feet from North / South Line of Section
2475 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Montgomery
Lease Name: Febrin Dalby Well #: 1 (C57)
Date Well Completed: 9-8-09
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 9-8-09
Plugging Completed: 9-8-09

KCC PDS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

30 sxs @1870' = 460' plug, gel spacer, 10 sxs @812' = 150' plug, gel spacer, 25 sxs 350' to surface

65 sx total to plug well This was an old well, no other information on this well.

RECEIVED
SEP 18 2009

KCC WICHITA

Plugging Contractor License #: 33961 Name: Consolidated Oil Well Service, LLC
Address 1: P. O. Box 884 Address 2: _____
City: Chanute State: KS Zip: 66720 + 0884
Phone: (620) 431-9210
Name of Party Responsible for Plugging Fees: Custer Oil & Gas, LLC
State of Oklahoma County, Osage, ss.
Gary Custer Employee of Operator or Operator on above-described well,
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: Norma Standridge, Agent

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

D-115



CONSOLIDATED
Oil Well Services, LLC

ENTERED

TICKET NUMBER 23591

LOCATION EUREKA

FOREMAN Kevin McCoy

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9-9-09	63104	Dowby # 1	SE 12	345	13E	MG
CUSTOMER Performance Group			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS P.O. Box 628			445	Justin		
CITY BARNSDALL			479	John S.		
STATE OK			437	Jim		
ZIP CODE 74002						

JOB TYPE P.T.A. HOLE SIZE _____ HOLE DEPTH _____ CASING SIZE & WEIGHT 4 1/2
 CASING DEPTH 1890' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT _____ DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety Meeting: Ran 2 3/8 Tubing in 4 1/2 Casing to Plug well. Spot Cement Plugs as following w/ 60/40 Pozmix 4% Gel, 3/4" /sk of Pheno Seal.

30 sks @ 1870' = 460' Plug

Gel Spacer

10 sks @ 812' = 150' Plug

Gel Spacer

25 sks 350' to SURFACE

65 sks Total to Plug well

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5405 A	1	PUMP CHARGE	590.00	590.00
5406	40	MILEAGE	3.45	138.00
1131	65 sks	60/40 Pozmix Cement	10.70	695.50
1118 A	225 #	Gel 4%	.16 #	36.00
1107 A	50 #	Pheno Seal 3/4" /sk	1.08 #	54.00
5407	2.80 Tons	Ton Mileage Bulk Truck	M/C	296.00
5502 C	5 Hrs	80 BBL VAC TRUCK	94.00	470.00
1123	3000 gals	City water	14.00/1000	42.00
1118 A	250 #	Gel (Gel Spacer)	.16 #	40.00
		RECEIVED		
		SEP 18 2009		
		KCC WICHITA		
		Sub Total		2361.50
		SALES TAX	5.3%	45.98
		ESTIMATED TOTAL		2407.48

THANK YOU

031116

AUTHORIZATION witnessed By PAUL

TITLE Partner

DATE 9-9-09