

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: Staab Oil Company
Address: 1607 Hopewell Rd., Hays, Ks 67601
Phone: (785) 625-5013 Operator License #: 6037
Type of Well: D & A Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 11-12-09 (Date)
by: Ed Schmucker (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)

API Number: 15-051-25,922 - 0000
Lease Name: Laurinda
Well Number: 1
Spot Location (QQQQ): _____ - NW - NW - NE
330 Feet from North / South Section Line
2,310 Feet from East / West Section Line
Sec. 25 Twp. 12 S. R. 18 East West
County: Ellis
Date Well Completed: 11-11-09
Plugging Commenced: 11-12-09
Plugging Completed: 11-12-09

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	230	Cmtd. w/150 sax

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.
Run drill pipe to 3,689', pump 25 sax cement thru drill pipe; run drill pipe to 1,415', pump 25 sax cement thru drill pipe; run drill pipe to 810', pump 100 sax cement thru drill pipe; run drill pipe to 280', pump 40 sax cement thru drill pipe; push wiper plug to 40', dump 10 sax cement on plug to cellar. Circulate 30 sax cement down rat hole and 15 sax cement down mouse hole.

Name of Plugging Contractor: Shields Oil Producers Inc License #: 5184
Address: PO Box 709, Russell, KS 67665

Name of Party Responsible for Plugging Fees: Staab Oil Company
State of KANSAS County, RUSSELL, ss.

Burton Beery Contractor
(Employee of Operator or Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) Burton Beery
(Address) PO Box 709, Russell, KS 67665

SUBSCRIBED and SWORN TO before me this 19th day of November, 2009

Leach Phillips Notary Public My Commission Expires: _____



Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED
NOV 20 2009

KCC WICHITA

Handwritten initials




Shields

Russell, Kansas

WELL LOG

Operator: Staab Oil Company
 Well: Laurinda #1
 Commenced: 11-5-09
 Completed: 11-12-09
 Contractor: Shields Drilling Co.

Well Description: 330' FNL, 2,310' FEL
 NE/4 Sec. 25-12S-18W
 Ellis Co., KS



CASING RECORD		
Size	Run	Pulled
8 5/8"	230'	Cmtd. w/150 sax

Elevation: 2,161' K.B.

Treatment:

Production: D & A

Tops:

..... Figures Indicate Bottom of Formations

Sand & shale	875'	
Sand	1,155'	
Sand & redbed	1,398'	
Anhydrite	1,432'	
Redbed & shale	2,045'	
Shale	2,795'	
Shale & lime	3,445'	
Lime	3,725'	
Arbuckle	3,749'	RTD

RECEIVED
 NOV 20 2009
 KCC WICHITA

Notes