

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 74-42
LOCATION NW NE SW
SEC. 25 TWP. 10 RGE. 20

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. _____ Lease Ouderkirk

Operator Tennessee Gas Transmission Address Box 103 Great Bend, Kans

Field _____ County Rooks

Total Depth 3700 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

10 3/4" at 191' circulated with cement - 7" 5095' with 200 sax
cement behind - 7" squeezed at approx 800'.

Filled with sand to 5090', set 4 sax cement with dump bailer, started
515' 7" - circulated hole with heavy mud at 500' (4/ sax Gel),
displaced 20 sax cement through 7" at 600', heavy mud to 170',
displaced 20 sax cement through 7", heavy mud to 30', set rock and
10 sax cement to bottom cellar.

Edouard Kelly
District Conservation Agent

Date 1-18-58

RECEIVED
STATE CORPORATION COMMISSION
1-22-1958
JAN 22 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 25 T 10 R 20 W
BOOK PAGE 74 LINE 43