

## DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
 Conservation Division  
 800 Bitting Building  
 Wichita, Kansas

FILE NO. 87-6LOCATION SE SW SWSEC. 25 TWP. 10 RGE. 20Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 5 Lease OuferkirkOperator Mid States Oil Corp Address 518 Natl Bk Bldg Tulsa,Field \_\_\_\_\_ County RooksTotal Depth 5753 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 301' circulated with cement - 7" at 3725' with  
150 sax cement behind - Lane Wells plugs to 3330' - top  
perforations at 3318'.

Filled with chat to 3300', set 5 sax cement with dump bailer,  
pulled 2218' 7", filled hole with mud to 250', set rock  
bridge and 20 sax cement, filled with mud to 35', set rock bridge  
and 10 sax cement to bottom cellar.

RECEIVED

STATE CORPORATION COMMISSION

8-15-1951  
AUG 15 1951

CONSERVATION DIVISION

Wichita, Kansas

District Conservation Agent

Date 8-9-51