

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 74-41

LOCATION SE NW SW

SEC. 25 TWP. 10 RGE. 20

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 2 Lease _____ Ouderkirk

Operator Tennessee Gas Transmission Address Box 163 Great Bend, Kans

Field _____ County Rooks

Total Depth ~~3374~~ 3091 Feet.

Plugging Contractor West Supply Co & Globe Cementing Co

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 1528' circulated with 750 sax cement - 5 1/2" 3074' with 200
sax cement behind - Filled with sand to 3060', set 4 sax cement with
dump bailer, pulled 2552' 5 1/2" to 700', circulated hole with heavy mud
through 5 1/2" at 700', (30 sax Gel), displaced 20 sax cement through
5 1/2" at 600', heavy mud to 400', displaced 20 sax cement through 5 1/2",
heavy mud to 35', set cementing plug, rock and 10 sax cement to
bottom cellar.

Mudding and cementing by Globe Cementing Co.

Edna Petty
District Conservation Agent

Date 1-10-58

RECEIVED
STATE CORPORATION COMMISSION
1-22-1958
JAN 22 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE NO. 25 T 10 R 20 W
BOOK PAGE 74 LINE 71