

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 74-40

LOCATION NW NW SW

SEC. 25 TWP. 10 RGE. 20

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Ouderkirk

Operator Tennessee Gas Transmission Address Box 163 Great Bend, Kans

Field _____ County Rooks

Total Depth 3715 Feet.

Plugging Contractor West Supply Co & Globe Cementing Co

Plugging Contractor's License No. 14

Address _____

(Describe Briefly the manner in which the well was plugged)

8 5/8" at 1503' circulated with cement - 5 1/2" 3702' with 200 sax
cement behind.

Filled with sand to 3690', set 4 sax cement with dump bailer, pulled
2019' 5 1/2" to 1000', circulated hole with heavy mud, displaced 20 sax
cement through 5 1/2" at 000', heavy mud to 240', displaced 20 sax
cement through 5 1/2" - heavy mud to 35', set rock and 10 sax cement
to bottom cellar.

Mudding and Cementing by Globe Cementing Co.

Edson Leaty
District Conservation Agent

Date 1-10-58

PLUGGING
FILE SEC. 25 T. 10 R. 204
BOOK PAGE 74 LINE 40

RECEIVED
STATE CORPORATION COMMISSION
1-14-1958
JAN 14 1958

CONSERVATION DIVISION
Wichita, Kansas