

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 36-2

LOCATION NE SW NW

SEC. 25 TWP. 10 RGE 20

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 3 Lease (Earl) Ruder

Operator Gulf Oil Co Address \_\_\_\_\_

Field \_\_\_\_\_ County Rooks

Total Depth 3771 Feet.

(Describe briefly the manner in which the well was plugged)  
600 sax.

8 5/8" at 1612' circulated with cement - 5 1/2" at 3745' with  
100 sax behind.

Filled with chat to 3740', set 5 sax cement with dump bailer,  
pulled Approx 3100' 5 1/2", filled hole with heavy mud to 250',  
set rock bridge and 15 sax cement, filled with heavy mud to  
40', set rock bridge and 10 sax cement to bottom cellar.

RECEIVED  
STATE CORPORATION COMMISSION  
10-23-1950  
OCT 23 1950

**PLUGGING**  
FILE SEC 25 TWP 10 R 20  
BOOK PAGE 36 LINE 2

*John J. Terry*  
District Conservation Agent

Date 10-19-50