

15-163-01155-0000

KANSAS

FORM CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGEN'T REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, Ks. 67202

API Number 15 - (151) (of this well)

Operator's Full Name POSTAL OIL & GAS CORPORATION
Complete Address P.O. BOX 1332 AMARILLO, TEXAS, 79189
Lease Name WILLIAMS Well No. #2
Location SE-SE-NW Sec. 27 Twp. 10 Rge. 20 (E) (W) W
County ROOFS Total Depth 3718
Abandoned Oil Well X Gas Well Input Well SWD Well D&A
Other well as hereafter indicated

Plugging Contractor HELSO CASING PULLING
Address BOX 176 CHASE, MS. 67524 License No. 683
Operation Completed: Hour 10:30 AM Day 31 Month Oct Year 1980

The Above well was plugged as follows:

8 5/8" 250ST SP. CUC w/150ST CMT. -> 5 1/2" SET @ 3709 w/100ST CMT.
PLUG. BACK 3673^{FE} -> PERFS 3566^{FE} - 3452^{FE}
SQUEEZED @ 1170^{FE} AND 987 w/290ST CMT. - NO PIPE RECOVERY.
ORDERED 170ST 50/50 POZMIX 6% GEL. -> 18ST GEL. -> 3ST HULL'S + 5 1/2" PLUG.
PUMPED IN WITH PUMP TRUCK.
PUT IN -> 2ST HULL'S - 50ST CMT. -> 18ST GEL - 1ST HULL'S.
RELEASED PLUG. AND 90ST CMT. - MAX PRESSURE 450 LBS
PUMPED 30ST CMT. IN ANNULUS. - MAX PRESSURE 200 LBS

RECEIVED
STATE CORPORATION COMMISSION
NOV - 3 1980

I hereby certify that the above well was plugged as herein stated.

CEMENTED BY ALLIED CMT

INVOICED
DATE 11-4-80
INV. NO. 3526-W

Signed: [Signature]
Well Plugging Supervisor

CONSERVATION DIVISION
Wichita, Kansas