

15-163-03433-0000

RECEIVED
STATE CORPORATION COMMISSION

JUL 21 1961

CONSERVATION DIVISION
Wichita, Kansas

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. _____ County: _____ Rooks _____

Location: NE NW SW Sec. 27 Twp. 10 Rge. _____ (E) _____ (W) 20

Name of Field: _____ Total Depth: 3679

I have this date completed supervision of plugging of:

Lease Name: Towns Well No. 2

Operator's Full Name: I. O. Miller

Complete Address: 619 Brown Bldg Wichita, Kansas

Plugging Contractor: Ace Pipe Pulling

Address: Great Bend, Kansas License No. 2

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes _____ No

If yes how long? _____ Reason: _____

Operation Completed: Hour 4PM Day 15 Month 7 Year 61

The above well was plugged as follows:

8 5/8" 230' circulated with cement - 5 1/2" 3676' with 75 sax cement. PB to
3515' - perforated 3430' - plugs and sand to 3400', set 5 sax cement with
dump bailer at 3400' - pulled 3300' 5 1/2" to 550', circulated hole with heavy
mud through 5 1/2" at 550' (20 sax Gel), displaced 20 sax cement through
5 1/2" at 550', heavy mud to 230', displaced 20 sax cement through 5 1/2" at 230',
heavy mud to 35', set bridge and 10 sax cement to bottom cellar.
Mudding and cementing by Globe Cementing Co.

Signed: [Signature]
Conservation Division Agent

Reviewed: [Signature]
Field Supervisor

Remarks:

INVOICED
DATE 8/7/61
INV. NO. 3498-11