

15-163-20539-0000

R

Form CP-3

Rev. 6-1-68

KANSAS

STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

AUG 09 1976

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

CONSERVATION DIVISION  
Wichita, Kansas

API Number 15 - - (of this well)

Operator's Full Name Calvin Noah

Complete Address 329 North Birch, Valley Center, Kansas 67147

Lease Name Sutor-Annon Well No. 2

Location NW SE NE Sec. 27 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3738'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 3 P Day 4 Month 8 Year 1976

The above well was plugged as follows:

Total Depth 3738' 8 5/8 csg set 207' cwc 190 sx.

5 1/2 csg set 3734' cw 100 sx cem.

Filled ~~4 1/2~~ <sup>5 1/2</sup> csg W/sd (3738'-3700') dumped 4 sx cem W/dump bailer. (3700'-3670')

Cutoff & recovered 3040' of 5 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs

hulls, followed with 70 sk cem. -displaced with 10 sk gel & water & capped with

50 sx cem. PP 400 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Bled Massey  
Well Plugging Supervisor

VOICED  
DATE 8/10/76  
INV. NO. 3609-W