

15-163-00946-0000

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

File No. \_\_\_\_\_ County: \_\_\_\_\_ Rooks

Location: SE NW SE \_\_\_\_\_ Sec. 27 Twp. 10 Rge. 20 (E) (W) \_\_\_\_\_

Name of Field: \_\_\_\_\_ Total Depth: 3702

I have this date completed supervision of plugging of:

Lease Name: Poague \_\_\_\_\_ Well No. 1

Operator's Full Name: Fender Pipe & Supply Co

Complete Address: Box 302 Russell, Kansas

Plugging Contractor: Barnes & Sons

Address: Russell, Kansas License No. 9

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour 10AM Day 16 Month 12 Year 60

The above well was plugged as follows:

8 5/8" 209' circulated with cement - 5 1/2" 3697' with 100 sax cement.  
Filled with sand to 3685' set 4 sax cement with dump bailer, pulled 3117'  
5 1/2" to 500', circulated hole with heavy mud ( 32 sax gel), displaced 20 sax  
cement through 5 1/2" at 500', Heavy mud to 160', displaced 20 sax cement  
through 5 1/2" at 160', heavy mud to 35', set bridge and 10 sax cement to  
bottom cellar.  
Mudding and cementing by Globe Cementing Co.

Signed: Jedon Petty  
Conservation Division Agent

Reviewed: J. Lewis Bush  
Field Supervisor

Remarks:

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 12-21-60  
COR  
WICHITA, KANSAS  
INVOICED  
DATE 12-23-60  
INV. NO. 279-W