

15-163-00296-0000

R

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

TO:
Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

File No. 128-21 County: Rooks

Location: SW SW NE Sec. 27 Twp. 10 Rge. 20 (E) (W)

Name of Field: _____ Total Depth: 3717

I have this date completed supervision of plugging of:

Lease Name: Annon Well No. 1

Operator's Full Name: Colorado Oil & Gas

Complete Address: Box 1050 Wichita, Kans

Plugging Contractor: West Supply Co

Address: Chase, Kans License No. 14

Oil Well Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated: _____

Was any delay in plugging operations caused by Conservation Division Agent? Yes ___ No ___

If yes how long? _____ Reason: _____

Operation Completed: Hour 5PM Day 25 Month 9 Year 58

The above well was plugged as follows:

8 5/8" at 253' circulated with cement - 5 1/2" 3711' with 125 sax cement
behind - hole in 5 1/2" in Dakota - 700' tubing and rods lost in hole.

Pulled 2593' 5 1/2" to 600', circulated hole with heavy mud through 5 1/2"
at 600' (35 sax Gel), displaced 20 sax cement through 5 1/2" at 600', heavy
mud to 150', displaced 20 sax cement through 5 1/2" - heavy mud to 55'
set bridge and 10 sax cement to bottom cellar.

Mudding and cementing by West Supply Co's pump truck.

Signed: Jewel M. Ogden
Conservation Division Agent

Reviewed: J. Lewis Brock
Field Supervisor

Remarks:

RECEIVED
STATE
OCT 1 10-01-58

PLUGGING
FILE SEC 27 T 10 R 20W
BOOK PAGE 128 LINE 21