

Make Copy

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION
Verbal
CONSERVATION DIVISION AGENT REPORT

API Number 15- -

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Nadel-Gussman (Frank Nefl)

Complete Address 2732 First National Tower - Tulsa, Okla 74103

Lease Name Eliza Well No. #2

Location SW NW SE Sec. 14 Twp. 10 Rge. 20 (East)(West)

County Rooks Total Depth 3773

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Used as Dakota water well 1964 to ?

Plugging Contractor Allied Cementing

Address Russell, Kansas License No. _____

Operation Completed: Hour: 10:00 Day: 16 Month: 9 Year: 19 82

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" @ 123' w/100 sx - cont. circ: 5 1/2" @ 3770' w/100 sx
P.B. - T.D. 3650' - 1953 squeezed @ 1100' w/250 sx cement (1700#)
1965 hole @ 920' not squeezed - pumped water from
Dakota for water flood - 5 1/2" csg cut-off below top of
8 5/8" - Hooked-up to 8 5/8" S.P. pumped 50 sx cement -> 200 sx
4 3/4 sx bulbs together - Reached 400# P.S.I while pumping -
pressure dropped while not pumping - Shut-in pressure 0 -
Used 250 sx 50# 62 gel - 3 1/2 sx bulbs over

Amount of Surface Casing: 123

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Samuel
Conservation Division Agent