

J.P.
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
12-8-1969
DEC 8 1969
CONSERVATION DIVISION
Wichita, Kansas
R. W.

Operator's Full Name I. O. Miller

Complete Address 619 Brown Bldg., Wichita, Kansas 67202

Lease Name Miller - Sutor Well No. 1

Location NW SW SE Sec. 14 Twp. 10 Rge. (E) (W) 20

County Rooks Total Depth 3784'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas License No. 49

Operation Completed: Hour 2P Day 4 Month 12 Year 1969

The above well was plugged as follows:

Total Depth 3784' 8 5/8 csg set at 177' cwc

5 1/2 csg set at 3780' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (3770-3784) Dumped 5 sk cmt W/dump bailer. (3730-3770)

Dakato Squeezed. Circulated to surface. No pipe recovered.

Filled 5 1/2 csg W/mud to 720'. Set rock bridge (705-720)

Filled with 4 1/2 yds readymix cmt. (0-705)

I hereby certify that the above well was plugged as herein stated.

Signed: *Leo J. Murray*
Well Plugging Supervisor

INVOICED
12/9/69
986-W