

KANSAS

AY STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name I. O. Miller Oil Co.

Complete Address: 619 Brown Bldg., Wichita, Kansas

Lease Name Sutor Well No. 7

Location C E/2 SW SE Sec. 14 Twp. 10 Rge. 20 (E) (W) X

County Rooks Total Depth 3780' 3794'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 8 A Day 4 Month 5 Year 1968

The Above well was plugged as follows:

Total Depth 3780' 8 5/8 csg set at ~~343'~~ 343' cwc 125 sc cement.

5 1/2 csg set at 3779' cw 125 sc cement.

5 1/2 DV tool set at 1698' cwc 650 sc.

Pushed plug to 2300', poured 25 gal sand and dumped 5 sc cement with dump bailer.

No pipe recov.

Mud to 230' and set 15 sc cement plug.

Mud to 40' and set 5 sc cement plug to surface.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: *R. F. Massey*
Well Plugging Supervisor

DATE 5/15/68
INV. NO. 7744-W