

KANSAS

FORM CP-3
Rev. 1-8-82

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15- -

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Nadel-Sussman (Frank Nadel)

Complete Address 3232 First National Tower - Tulsa, OK 74103

Lease Name Stithem Well No. 1

Location NW-NW-NW Sec. 14 Twp. 10 Rge. 20 (East)(West)

County Rooks Total Depth 3778

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Allied Cementing

Address Russell, Kansas License No. _____

Operation Completed: Hour: 11:00 Day: 16 Month: 9 Year: 1982

Plugging Operations attended by Agent?: All Part None

The above well was plugged as follows:

8 5/8" @ 163' w/125 sy - 5 1/2" @ 3775 w/100 sy

P.B. 3700 - 1959 hole @ 1137' squeezed w/235 sy 1400#:

1976 hole @ 823' not squeezed. 5 1/2" csg cut off below 8 5/8" top:

Pumped in 8 5/8" & 5 1/2" at same time: Rmpt 50 cmt ->

200 cmt. + 3hulls together: Reached 800# P.S.I. while pumping.

Shut in @ 200# P.S.I. - Used 250 sy 3/8" psg 6% gel & 3hulls

(Allied)

Amount of Surface Casing: 168'

I hereby certify that the above plugging instructions were given as herein stated.

Signed: Dennis L. Harnel
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED
STATE CORPORATION COMMISSION
SEP 27 1982
7-27-1982
CONSERVATION DIVISION
Wichita, Kansas

Signed: _____
Conservation Division Agent

10-8-82
1302 w
B