

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RCWD
05-10-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name I. O. Miller Oil Co.

Complete Address: 619 Brown Bldg., Wichita, Kansas

Lease Name Sutor Well No. 2

Location SW SW SE Sec. 14 Twp. 10 Rge. 20 (E) (W) X

County Rooks Total Depth 3794

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 10 A Day 4 Month 5 Year 1968

The Above well was plugged as follows:

Total Depth 3794' 8 5/8 csg set at 188' cwc.

5 1/2 csg set at 3774' cw 150 sc cement.

Filled with sand to 3770' and dumped 5 sc cement with dump bailer.

Recov. 478' of 5 1/2 csg.

Pumped thru 8 5/8 swage with 1 hull, 100 sc cement, 5 gel, 2 hull and 25 sc cement.

Cement (0-100) gel (100-300) cement (300-700) mud 700 to TD.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 5/15/68
INV. NO. 4741-W